


Estimation of costs associated with CO₂ based EOR projects - revised report

Delivery D4.1.4


Nils Henrik Eldrup
14 06 2011

PIE 14-06-2011
Georg Hegerland
Knut Kr. Osnes
Trygve Sæther

Estimation of costs - elements



The General Oil Field, Case description



General Oil Field (GOF) - description

GOF input data	
Wellhead pressure after choking (bars)	85
Temperature (°C)	70
Oil and gas (% of plateau prod.)	15
Oil production (bbl/day)	37 500
Water quantity (% by wt of oil/water mix)	90
HC gas production (% by wt of oil/gas mix)	7.5
CO ₂ gas injected (kton/year)	5 000
Recovery (80% of injected) (kton/year)	4 000
H ₂ S	Yes (high)

Membrane separation

- Known membranes give CO₂ as permeate at low pressure.
- No reference to more than 75 vol% CO₂ inlet.

Requirements:


- ✓ Large membrane area
- ✓ Expensive recompression
- ✓ Development of better membranes?

Consequence:

- ✓ Fuel gas production at GOF is probably not realistic

Qualitative cost for fuel gas production

Item		Investment (Capex)	Operational cost (Opex)
7	Membrane pretreatment	Medium	Moderate
8	Membranes	Very large	Low
13	Permeate recompression	Large	Large
14	Permeate cooler	Large	Moderate



Offshore cost, man-hour compared to base cost from contractor.

Cost element	Base	Offshore (EUR/hour)
Base cost from contractor	100 EUR/hour	100 EUR/hour
Travel and accomodation	250 EUR/day	33 EUR/hour
Efficiency	50 %	133 EUR/hour
Temporary facilities	0 %	0
Adjusted man-hour rate		267 EUR/hour

Estimation alternatives

Item no	Equipment	Max CAPEX Alt. 1	Min CAPEX & New rotors Alt. 2	Min CAPEX Alt. 3
0	Pre separator	New	New	New
1	Inlet separator	New	Existing	Existing
2	Middle separator	New	Existing	Existing
3	Outlet separator	New	Existing	Existing
4	CO ₂ separator	New	New	New
5	Glycol drying unit	Existing	Existing	Existing
6	H ₂ S scavenger	Existing	Existing	Existing
7	Membrane pretreatment [Fuel gas]	New	New	New
8	Membrane separator [Fuel gas]	New	New	New
9	Low pressure compressor	New	New rotor	Existing
10	Medium pressure compressor	New	New rotor	Existing
11	High pressure compressor	New	New rotor	Existing
12	Gas cooler	New	New	New
13	Permeate compressor [Fuel gas]	New	New	New
14	Permeate cooler [Fuel gas]	New	New	New

Equipment list General Oil Field

Tag no	Equipment description	Size	Unit	Pressure (bar)	Temp in C	Temp out C	Material
0	Pre-separator	37	m3	85			SS316
1	Inlet separator	Existing					
2	Middle separator	Existing					
3	Outlet separator	Existing					
4	CO2 water separator	150	m3	1,5			SS316
5	Glycol drying unit	Existing					
6	H2S scavenger	Existing					
7	Membrane pre treatment	Not included in the cost estimate					
8	Membrane separator	Not included in the cost estimate					
9	LP Compressor, internals only	6300	kW	12	66	300	
10	MP Compressor, internals only	4000	kW	55	45	134	
11	HP Compressor, internals only	10000	kW	125	44	114	
12	Gas cooler CO2 side	40	MW	125	114	25	SS316
12	Gas cooler sea water side	950	m2	3	5	30	Titanium
13	Permeate compressor	Not included in the cost estimate					
14	Permeate cooler	Not included in the cost estimate					

Cost estimate			
	Max CAPEX	Min CAPEX & New rotors	MIN CAPEX
	kEUR	kEUR	kEUR
Equipment costs	13 428	5 622	2 068
Erection cost	3 851	4 775	746
Piping incl. Erection	13 121	4 358	2 636
Electro (equip & erection)	7 589	2 112	1 267
Instrument (equip. & erection)	8 741	2 582	1 659
Ground work	3 239	906	547
Steel & concrete	7 651	2 150	1 306
Insulation	1 125	339	222
Direct costs	58 744	22 844	10 452
Engineering process	597	432	102
Engineering mechanical	249	114	49
Engineering piping	1 066	484	202
Engineering el.	594	265	100
Engineering instr.	717	326	137
Engineering ground	120	53	21
Engineering steel & concrete	358	160	62
Engineering insulation	54	25	11
Engineering	3 756	1 858	684
Procurement	124	83	41
Project control	207	149	38
Site management	6 845	3 025	1 084
Project management	5 618	2 484	894
Administration	12 793	5 741	2 057
Commissioning	2 199	1 346	427
Identified costs	77 493	31 789	13 620
Contingency	15 499	6 358	2 724
Total costs 2009	92 992	38 147	16 344

Conclusions (1)

1. Difficulties

- CO₂ breakthrough in the associated gas is unavoidable (after lag time).
- A major part of the CO₂ injected will break through and end up in the associated gas.
- CO₂ and water in carbon steel equipment will cause unacceptable corrosion.
- Modifications of an offshore platform are cumbersome and costly.
- Loss of oil production due to shutdowns to carry out platform modifications will have large economical implications.
 - Shut down time (loss of income) critical to overall project economy
- The supply of CO₂ to an offshore oil field will be costly.

Conclusions (2)

2. Advantages

- Postponed field close down - effects on close down costs
- Prolonged field lifetime – increased overall oil yield
- Part of the CO₂ quantity will be stored permanently

- Detailed engineering to be done for a concrete field
 - HES modifications, OPEX etc..

Conclusions (3)

The required and preferred oil field / platform conditions are:

- The equipment and piping are made of non corroding steel, to withstand corrosion caused by sulphur components and CO₂.
- The selected field should have a low gas oil ratio (GOR) when starting the EOR
- The field should be at the end of its lifetime and operating with low associated gas quantity to secure capacity for handling the break through CO₂ with least possible platform modifications.
- Previously drilled wells for WAG injection may be used for CO₂ injection. Costs for injection well modifications have hence not been estimated in this study.
- The platform should have an alternative energy supply not requiring fuel gas production from the associated gas. The untreated associated gas therefore can be reinjected after breakthrough of CO₂.
Fuel gas production from the GOF associated gas, > 90 vol% CO₂, may not be feasible or economical
- A secure and sufficient external CO₂ supply must be available at a reasonable cost. The required quantity for CO₂ will drop considerably at CO₂ break through.

Alt. 1:
New equipment and
renewing the
Separation and
Compressor train

	IBL Equipment	IBL Bulk materiel	IBL Hour Cost	Sum
	kEUR	kEUR	kEUR	kEUR
Equipment costs	13 428	0	0	13 428
Erection cost		0	3 851	3 851
Piping incl. Erection		3 272	9 849	13 121
Electro (equip & erection)		1 070	6 519	7 589
Instrument (equip. & erection)		862	7 879	8 741
Ground work		213	3 027	3 239
Steel & concrete		1 078	6 572	7 651
Insulation		159	966	1 125
Direct costs	13 428	6 653	38 664	58 744
Engineering process			597	597
Engineering mechanical			249	249
Engineering piping			1 066	1 066
Engineering el.			594	594
Engineering instr.			717	717
Engineering ground			120	120
Engineering steel & concrete			358	358
Engineering insulation			54	54
Engineering			3 756	3 756
Procurement			124	124
Project control			207	207
Site management			6 845	6 845
Project management			5 618	5 618
Administration			12 793	12 793
Commissioning			2 199	2 199
Identified costs				77 493
Contingency				15 499
Total costs 2009	13 428	6 653	57 412	92 992

Alt. 2:
New equipment and
renewing the
Separation and new
rotors in the
Compressors

Cost estimate				
	IBL Equipment	IBL Bulk materiel	IBL Hour Cost	Sum
	kEUR	kEUR	kEUR	kEUR
Equipment costs	5 622	0	0	5 622
Erection cost		0	4 775	4 775
Piping incl. Erection		953	3 405	4 358
Electro (equip & erection)		298	1 814	2 112
Instrument (equip. & erection)		255	2 328	2 582
Ground work		60	847	906
Steel & concrete		303	1 847	2 150
Insulation		48	291	339
<u>Direct costs</u>	<u>5 622</u>	<u>1 916</u>	<u>15 307</u>	<u>22 844</u>
Engineering process			432	432
Engineering mechanical			114	114
Engineering piping			484	484
Engineering el.			265	265
Engineering instr.			326	326
Engineering ground			53	53
Engineering steel & concrete			160	160
Engineering insulation			25	25
<u>Engineering</u>			<u>1 858</u>	<u>1 858</u>
Procurement			83	83
Project control			149	149
Site management			3 025	3 025
Project management			2 484	2 484
<u>Administration</u>			<u>5 741</u>	<u>5 741</u>
Commissioning			<u>1 346</u>	<u>1 346</u>
<u>Identified costs</u>				<u>31 789</u>
Contingency				<u>6 358</u>
<u>Total costs 2009</u>	<u>5 622</u>	<u>1 916</u>	<u>24 252</u>	<u>38 147</u>

Alt. 3: New equipment

	IBL Equipment	IBL Bulk materiel	IBL Hour Cost	Sum
	kEUR	kEUR	kEUR	kEUR
Equipment costs	2 068	0	0	2 068
Erection cost		0	746	746
Piping incl. Erection		767	1 869	2 636
Electro (equip & erection)		179	1 089	1 267
Instrument (equip. & erection)		164	1 495	1 659
Ground work		36	511	547
Steel & concrete		184	1 122	1 306
Insulation		31	191	222
<u>Direct costs</u>	<u>2 068</u>	<u>1 360</u>	<u>7 023</u>	<u>10 452</u>
Engineering process			102	102
Engineering mechanical			49	49
Engineering piping			202	202
Engineering el.			100	100
Engineering instr.			137	137
Engineering ground			21	21
Engineering steel & concrete			62	62
Engineering insulation			11	11
<u>Engineering</u>			<u>684</u>	<u>684</u>
Procurement			41	41
Project control			38	38
Site management			1 084	1 084
Project management			894	894
<u>Administration</u>			<u>2 057</u>	<u>2 057</u>
Commissioning			<u>427</u>	<u>427</u>
<u>Identified costs</u>				<u>13 620</u>
Contingency				<u>2 724</u>
Total costs 2009	2 068	1 360	10 192	16 344